



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD
Chottanikkara temple – Providing Queue system in connection with Makam
Festival of 1199 ME.

- Read
1. Note from AE dt. 22-01-2024
 2. Note from AEE dt. 27-01-2024
 3. Note from EE dt. 27-01-2024
 4. Decision of DC dt. 31-01-2024

Order on H1. 144/24 dt. 31-01-2024

As per the papers cited above an estimate of Rs. 96,000/- (Rupees Ninety six thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 07-02-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Chottanikkara for exhibiting in their office Notice boards.

(By Order)

Sd/-

D. Suni

Assistant Executive Engineer

To

Notice Board, AC- Chottanikkara,
CA to DC, EE, AEE, AE,
S.F,

//Approved for issue//

[Handwritten signature]

For Junior Superintendent

PRICE

EST NO:2024/1704

TS Register No: 3914/2023-2024

AS Register No:4113/2023-2024

**Providing Department Que System in Connection with Makam Festival
atChottanikkara Temple**

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

1 Fixing Devaswom queue system	
1	od306432/2023_2024 labour charges for fixing Devaswom steel barricade of size 2.40 m x 1.50 m or simillar. Steel barricade tied with metal wire or plastic rope to GI post 32 mm dia 2.00 m height placed into the pit already made, after cleaning the pits including all charges for erection including all transportation charges, loading, unloading, and dismantling after the function stacking etc complete. Pipes should be enamel painted and holes should be closed by caps or cement mortar after dismantling barricades
Net Total Quantity 525.000 metre	
Say 525.000 metre @ Rs 121.68 / metre Rs 63882.00	
2 Miscellaneous work	
1	od306450/2023_2024 Extra Labors Fitter(grade1)
Net Total Quantity 15.000 Day	
Say 15.000 Day @ Rs 1162.26 / Day Rs 17433.90	
Service Tax @ 18.0%	
Service Tax Amount 14636.86	
Total with Service Tax Amount 95952.86	
Lumpsum for round off 47.14	
TOTAL Rs 96000.00	
Rounded Total Rs 96,000	
Rupees Ninety Six Thousand Only	

(Cost Index Applied for this estimate is 35.59%)