



## PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

### Abstract

Cochin Devaswom Board – Maramath wing- Repairs to Girls toilet at Sree Vivekananda College, Kunnankulam – Thrissur Group- Quotations invited – Order issued

- Read
1. Letter from SVC Principal
  2. Note from AE dt. 05-06-2024
  3. Note from AEE dt. 10-06-2024
  4. Note from EE dt. 10-06-2024
  5. Decision of DC dt. 12-06-2024

Order on H1. 1200/2024 dt. 25-06-2024

As per the papers cited above an estimate of Rs. 1,77,000/- (Rupees One lakh and seventy seven thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 04-07-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.


A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur group for exhibiting in their office Notice boards.

(By Order)  
Sd/-  
K. Sreeja  
Assistant Engineer

To

Notice Board, ~~The~~ Principal, Sree Vivekananda College,  
The Assistant Commissioner - Thrissur,  
The Devaswom Commissioner, The Executive Engineer ,  
The Assistant Executive Engineer,  
The Assistant Engineer, Stock File

//Approved for issue//

*for*   
Junior Superintendent  
Senior Clerk

**REPAIR OF GIRLS TOILET AT SVC COLLEGE-KUNNAMKULAM-THRISSUR****GROUP**

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

<b>1 cement concrete</b>	
1	4.1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)
Net Total Quantity	
1.522 cum	
Say 1.522 cum @ Rs 7367.55 / cum	
<b>Rs 11213.41</b>	
<b>2 cement platering</b>	
1	13.1.1 12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)
Net Total Quantity	
35.020 sqm	
Say 35.020 sqm @ Rs 314.09 / sqm	
<b>Rs 10999.43</b>	
<b>3 Dadoing</b>	
1	11.37A Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS :15622 (thickness to be specified by the manufacturer ) of approved make in allcolours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thickbed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cementslurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.
Net Total Quantity	
24.419 sqm	
Say 24.419 sqm @ Rs 1092.18 / sqm	
<b>Rs 26669.94</b>	
<b>4 Ceramic floor tiling</b>	
1	11.37 Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc., complete.
Net Total Quantity	
16.661 sqm	
Say 16.661 sqm @ Rs 1091.02 / sqm	
<b>Rs 18177.48</b>	
<b>5 25mm PVC pipe,10Kgf/cm2</b>	