



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Minor repairs to Assistant Commissioner Office building – Thrissur group.

- Read
1. Note from AE dt. 25-03-2024
 2. Note from AEE dt. 26-03-2024
 3. Note from EE dt. 26-03-2024
 4. Decision of DC dt. 01-04-2024

Order on H1. 233/2024 dt. 01-04-2024

As per the papers cited above an estimate of Rs. 4,98,000/- (Rupees Four lakh and ninety eight thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 08-04-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur for exhibiting in their office Notice boards.

(By Order)
Sd/-
K. Sreeja
Assistant Engineer

To

Notice Board, AC- Thrissur,
CA to DC, EE, AEE, AE ,S.F,

//Approved for issue//

Junior Superintendent

TS Register No: 17/2024-2025

AS Register No:4/2024-2025

MINOR REPAIR TO AC OFFICE BUILDING -THRISSUR GROUP

Abstract Estimate

(Dsr year: 2018, Cost Index Applied for this estimate is 35.59%)

1 DISMANTLING ROOF		
1	15.31 Dismantling tiled roofing with battens, boarding etc. complete including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	
Net Total Quantity		344.064 sqm
Say 344.064 sqm @ Rs 176.54 / sqm		Rs 60741.06
2	od377425/2023_2024 Dismantling tiled roofing's roof tile only complete including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	
Net Total Quantity		344.064 sqm
Say 344.064 sqm @ Rs 105.93 / sqm		Rs 36446.70
3	15.14.1 Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead:Of sectional area 40 square centimetres and above	
Net Total Quantity		0.500 cum
Say 0.500 cum @ Rs 3938.41 / cum		Rs 1969.21
2 RESETTING AND WOOD WORK		
1	od345886/2023_2024 Supplying and fixing Dept. wood wrought and put up for roof members including cost and conveyance of materials etc. complete.	
Net Total Quantity		0.200 cum
Say 0.200 cum @ Rs 41616.15 / cum		Rs 8323.23
2	od345888/2023_2024 Supplying and fixing Anjily wood wrought and put up for roof members including cost and conveyance of materials etc. complete .	
Net Total Quantity		0.200 cum
Say 0.200 cum @ Rs 127438.09 / cum		Rs 25487.62
3	od345889/2023_2024 Refitting old wood work etc complete.	
Net Total Quantity		0.100 cum
Say 0.100 cum @ Rs 7601.42 / cum		Rs 760.14