



## PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Repairs to western Nadapanthal and constructing shed in front of south toilet at Thriprayar temple.

- Read
1. Report of DAC Thrissur on R1. 5670/22 dt. 25-01-2024
  2. Note from AE dt. 06-06-2024
  3. Note from AEE dt. 06-06-2024
  4. Note from EE dt. 06-06-2024
  5. Decision of DC dt. 06-06-2024

Order on H1. 208/2024 dt. 07-06-2024

As per the papers cited above an estimate of Rs. 4,70,000/- (Rupees Four lakh and seventy thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 14-06-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.


A copy of the estimate along with notification is herewith forwarded to Devaswom Commissioner Devaswom Assistant Commissioner, Thrissur for exhibiting in their office Notice boards.

(By Order)  
Sd/-  
M.K. Dileep  
Assistant Engineer

To

✓ Notice Board, AC- Thrissur,  
CA to DC, EE, AEE, AE ,S.F,

//Approved for issue//

  
Junior Superintendent

**Repairs to western nadapanthal and constructing shed in front of south toilet at  
Thriprayar temple**

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

<b>1 Earth work and concreting</b>	
1	2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil
Net Total Quantity	
0.500 cum	
Say 0.500 cum @ Rs 214.03 / cum	
<b>Rs 107.02</b>	
2	5.1.3 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 ( 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)
Net Total Quantity	
1.000 cum	
Say 1.000 cum @ Rs 8588.47 / cum	
<b>Rs 8588.47</b>	
<b>2 Roof</b>	
1	10.2 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.
Net Total Quantity	
300.000 kg	
Say 300.000 kg @ Rs 119.79 / kg	
<b>Rs 35937.00</b>	
2	10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.
Net Total Quantity	
185.600 kilogram	
Say 185.600 kilogram @ Rs 101.29 / kilogram	
<b>Rs 18799.42</b>	
3	12.50 Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.