



## PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

### Abstract

Cochin Devaswom Board – Maramath wing- Enhancing facilities inside Thidapilly of Sree Nelluvai Dhanwanthari temple– Nelluvai Devaswom – Thiruvilwamala Group- Quotations invited – Order issued

- Read
1. Request from temple Thanthri Sri. Kizhumundayoor Neelakandan Namboothiri dt. 04-08-2024
  2. Letter from DAC Thiruvilwamala on Rs. 4061/24 dt. 09-08-2024
  3. Note from AE dt. 24-08-2024
  4. Note from AEE dt. 30-08-2024
  5. Note from EE dt. 30-08-2024
  6. Decision of DC dt. 03-09-2024

Order on H1. 1708/2024 dt. 03-09-2024

As per the papers cited above an estimate of Rs. 2,90,000/- (Rupees Two lakh and Ninety thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 10-09-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thiruvilwamala group for exhibiting in their office Notice boards.

(By Order)

Sd/-

S. Gopakumar

Assistant Engineer

To

Notice Board,  
The Assistant Commissioner - Thiruvilwamala,  
The Devaswom Commissioner, The Executive Engineer ,  
The Assistant Executive Engineer,  
The Assistant Engineer, Stock File

//Approved for issue//

*[Signature]*  
for Junior Superintendent  
Senior Clerk

TS Register No: 1261/2024-2025

AS Register No:1305/2024-2025

**Renovation of 'Thidappilly' inside of Sree Nelluvai Dhanwanthari Temple-Nelluvai  
Devaswom - Thiruvilwamala Group**

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

<b>1 Dismantling</b>		
1	15.14.1 Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead:Of sectional area 40 square centimetres and above	
Net Total Quantity		0.180 cum
Say 0.180 cum @ Rs 3938.41 / cum		<b>Rs 708.91</b>
2	15.2.2 Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge.Nominal concrete 1:4:8 leaner mix ( including equivalent design mix)	
Net Total Quantity		1.539 cum
Say 1.539 cum @ Rs 1262.82 / cum		<b>Rs 1943.48</b>
<b>2 Earthwork</b>		
1	2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil	
Net Total Quantity		6.155 cum
Say 6.155 cum @ Rs 214.03 / cum		<b>Rs 1317.35</b>
<b>3 Supplying and fixing new granite cutstone pillars with necessary supporting pothikas and basement.(Approximate length/height=1.75 M),2 Nos</b>		
Lump-Sum Total		<b>Rs 30000.00</b>
<b>4 Flooring</b>		
1	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	
Net Total Quantity		3.326 cum
Say 3.326 cum @ Rs 7990.86 / cum		<b>Rs 26577.60</b>