



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD
Rewiring of Thiruvilwamala Assistant Commissioner Office/Oottupura.

- Read
1. Report of DAC Thiruvilwamala on M2. 1072/24 dt. 28-02-2024
 2. Note from AE (Electrical) dt. 20-03-2024
 3. Note from AEE dt. 20-03-2024
 4. Note from EE dt. 20-03-2024
 5. Decision of DC dt. 23-03-2024

Order on H1. 495/2024 dt. 30-03-2024

As per the papers cited above an estimate of Rs. 2,40,000/- (Rupees Two lakh and forty thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 08-04-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thiruvilwamala for exhibiting in their office Notice boards.

(By Order)


Sd/-

V.K. Ramakrishnan
Assistant Engineer (Electrical)

To

✓ Notice Board, AC- Thiruvilwamala,
CA to DC, EE, AEE, AE(Electrical) ,S.F,

//Approved for issue//


Junior Superintendent

Rewiring of Thiruvilwamala Asst. Commissioner's office and connected Electrics.

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

1 wiring	
1	1.10.2 Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLSPVC insulated copper conductor single core cable etc as required. Group B
Net Total Quantity	
53.000 point	
Say 53.000 point @ Rs 930.15 / point	
Rs 49297.95	
2	1.17.3 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 X 1.5 sq.mm
Net Total Quantity	
43.000 metre	
Say 43.000 metre @ Rs 63.73 / metre	
Rs 2740.39	
3	1.17.12 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 x 2.5 sq. mm
Net Total Quantity	
107.000 metre	
Say 107.000 metre @ Rs 89.49 / metre	
Rs 9575.43	
4	1.21.1 Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required. 20 mm
Net Total Quantity	
110.000 metre	
Say 110.000 metre @ Rs 98.98 / metre	
Rs 10887.80	
5	1.31 Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. (For light plugs to be used in non residential buildings).
Net Total Quantity	
4.000 each	
Say 4.000 each @ Rs 477.28 / each	
Rs 1909.12	
6	1.33 Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc as required.
Net Total Quantity	
43.000 each	

