



PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

Abstract

Cochin Devaswom Board – Maramath wing- Reconstructing damaged compound wall at Puranattukara temple Poornkunnam Devaswom - Thrissur - Quotations invited –
Order issued

- Read
1. Letter from DO dt. 17-10-2024
 2. Note from AE dt. 18-10-2024
 3. Note from AEE dt. 18-10-2024
 4. Note from EE dt. 18-10-2024
 5. Decision of DC dt. 22-10-2024

Order on H1. 2067/2024 dt. 23-10-2024

As per the papers cited above an estimate of Rs. 3,95,000/- (Rupees Three lakh and ninety five thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 05-11-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur for exhibiting in their office Notice boards.

(By Order)

Sd/-

K. Sreeja

Assistant Engineer

To

~~Notice Board,~~
The Assistant Commissioner, Thrissur,
The Devaswom Commissioner,
The Executive Engineer,
The Assistant Executive Engineer,
The Assistant Engineer, Stock File

//Approved for issue//

Junior Superintendent

**Reconstructing damaged compound wall at Puranattukara temple - Poonkunnam
devaswom - Thrissur group II**

Abstract Estimate

(Dsr year: 2018, Cost Index Applied for this estimate is 35.59%)

1 compound wall	
1	od151648/2024_2025 Extra Labours Labour- Mate
Net Total Quantity	
15.000 Day	
Say 15.000 Day @ Rs 971.70 / Day	
Rs 14575.50	
2	2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil
Net Total Quantity	
13.500 cum	
Say 13.500 cum @ Rs 214.03 / cum	
Rs 2889.41	
3	60.7.1 DRY RUBBLE MASONRY _ Dry rubble without concrete levelling course masonry with good quality blasted rubble including packing to compactness to lines and levels cost and conveyance of all materials labour charges etc. complete as per direction of Departmental officers at site
Net Total Quantity	
10.125 cum	
Say 10.125 cum @ Rs 3491.44 / cum	
Rs 35350.83	
4	5.9.1 Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings, bases of columns, etc for mass concrete
Net Total Quantity	
4.500 sqm	
Say 4.500 sqm @ Rs 335.31 / sqm	
Rs 1508.90	
5	5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1.5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size
Net Total Quantity	
3.375 cum	
Say 3.375 cum @ Rs 9085.14 / cum	
Rs 30662.35	
6	5.22.1 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelMild steel and Medium Tensile steel bars
Net Total Quantity	
202.500 kg	