



## PROCEEDINGS OF THE COCHIN DEVASWOM BOARD

### Abstract

Cochin Devaswom Board – Maramath wing- Providing truss work above Devaswom Office at Kachanapilly temple – Kachanapilly Devaswom – Thrissur Group- Quotations invited – Order issued

- Read
1. Note from AE dt. 27-09-2024
  2. Note from AEE dt. 30-09-2024
  3. Note from EE dt. 30-09-2024
  4. Decision of DC dt. 07-10-2024

Order on H1. 1499/2024 dt. 14-10-2024

As per the papers cited above an estimate of Rs. 4,10,000/- (Rupees Four lakh ten thousand only) is passed and sanction is accorded to execute the above work after inviting local quotations.

The sealed quotations should be received in this office on or before 25-10-2024 at 3 P.M. and will be opened at 3.30 P.M. on the same day in the presence of Executive Engineer, Cochin Devaswom Board/higher officials of Cochin Devaswom Board, Thrissur.

The sealed quotations should be addressed to the Executive Engineer, Cochin Devaswom Board, Thrissur and should contain the PAN number of the quotationer.

A copy of the estimate along with notification is herewith forwarded to Devaswom commissioner Devaswom Assistant Commissioner, Thrissur group for exhibiting in their office Notice boards.

(By Order)  
Sd/-  
M.K. Dileep  
Assistant Engineer

To

✓ Notice Board,  
The Assistant Commissioner - Thrissur,  
The Devaswom Commissioner,  
The Executive Engineer ,  
The Assistant Executive Engineer,  
The Assistant Engineer, Stock File

//Approved for issue//

For   
Junior Superintendent  
Senior clerk

TS Register No: 1661/2024-2025

AS Register No:1710/2024-2025

Providing truss work above devaswom office at kachanapilly temple, KachanappillyDevaswom

Abstract Estimate

(Dsor year: 2018, Cost Index Applied for this estimate is 35.59%)

| 1 Truss work                      |   |
|-----------------------------------|---|
| 1                                 | od100796/2024_2025<br>Steel work in built up G P tubular ( round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete   |
| Net Total Quantity                |   |
| 700.000 kg                        |   |
| Say 700.000 kg @ Rs 169.45 / kg   |   |
| <b>Rs 118615.00</b>               |   |
| 2                                 | od100802/2024_2025<br>Steel work for purlin/single section with G P pipes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete  |
| Net Total Quantity                |   |
| 430.000 kg                        |   |
| Say 430.000 kg @ Rs 129.62 / kg   |   |
| <b>Rs 55736.60</b>                |   |
| 3                                 | 4.1.3<br>Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)  |
| Net Total Quantity                |   |
| 1.600 cum                         |   |
| Say 1.600 cum @ Rs 7990.86 / cum  |   |
| <b>Rs 12785.38</b>                |   |
| 4                                 | 12.50<br>Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. |
| Net Total Quantity                |   |
| 175.000 sqm                       |   |
| Say 175.000 sqm @ Rs 738.69 / sqm |   |
| <b>Rs 129270.75</b>               |   |
| 5                                 | od100803/2024_2025<br>Providing and fixing PVC square gutter including jointing of pipes with one step pvc solvent cement, testing of joints complete as per direction of Engineer in charge 150 mm dia   |
| Net Total Quantity                |   |
| 70.000 metre                      |   |

|   |  |                                    |
|---|--|------------------------------------|
|   | Say 70.000 metre @ Rs 250.34 / metre   | <b>Rs 17523.80</b>                 |
| 6 | od100805/2024_2025<br>Supplying and fixing PVC square gutter end cap 150mm   |                                    |
|   | Net Total Quantity   | 10.000 each                        |
|   | Say 10.000 each @ Rs 174.23 / each   | <b>Rs 1742.30</b>                  |
| 7 | od100806/2024_2025<br>Supplying and fixing PVC square gutter down fall 150mm   |                                    |
|   | Net Total Quantity   | 10.000 each                        |
|   | Say 10.000 each @ Rs 174.23 / each   | <b>Rs 1742.30</b>                  |
| 8 | 50.18.9.18.2<br>Providing and fixing PVC pipes including fixing the pipe with clamps/Clips at 1.00 m spacing. This included jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 75 mm dia 4 Kfg/cm2 - External work - Exposed on wall |                                    |
|   | Net Total Quantity   | 35.000 metre                       |
|   | Say 35.000 metre @ Rs 240.25 / metre   | <b>Rs 8408.75</b>                  |
|   | Service Tax @  | <b>18.0%</b>                       |
|   | Service Tax Amount   | <b>62248.48</b>                    |
|   | Total with Service Tax Amount  | <b>408073.48</b>                   |
|   | Lumpsum for round off  | <b>1926.52</b>                     |
|   |  | <b>TOTAL Rs 410000.00</b>          |
|   |  | <b>Rounded Total Rs 4,10,000</b>   |
|   |  | Rupees Four Lakh Ten Thousand Only |

(Cost Index Applied for this estimate is 35.59%)